New Jersey Department of Transportation
1035 Parkway Avenue, PO Box 600, Trenton, New Jersey 08625-0600

Baseline Document Change Announcement

ANNOUNCEMENT: BDC25S-18

DATE: February 12, 2026

SUBJECT: Excavation, Test Pit
- **Revisions to Subsection 202.02 and Subpart 202.03.02 of the 2019 Standard Specifications for Road and Bridge Construction**

Subsection 202.02 and Subpart 202.03.02 of the 2019 Standard Specifications for Road and Bridge Construction are being revised to include traffic control and pavement restoration under the EXCAVATION, TEST PIT Pay Item.

The following revisions have been incorporated into the 2019 Standard Specifications via 2019 Standard Inputs, SI2019:

202.02 Materials
THE FOLLOWING MATERIALS ARE ADDED:

Dense-Graded Aggregate 901.10
HMA 902.02

202.03.02 Excavation, Test Pit
THE FOLLOWING IS ADDED AFTER THE LAST PARAGRAPH:

For test pits within the existing pavement structure, backfill and restore the pavement structure to match the surrounding pavement. Provide necessary traffic control during the test pit operation.

Implementation Code R (ROUTINE)

Changes must be implemented in all applicable Department projects scheduled for Final Design Submission at least one month after the date of the BDC announcement. This will allow designers to make necessary plan, specifications, and estimate/proposal changes without requiring the need for addenda or postponement of advertisement or receipt of bids.

Recommended By:

Tina M. Shutz

Tina Shutz
Director
Capital Program Support

Approved By:

Parth Oza

Parth Oza, P.E.
Assistant Commissioner
Capital Program Management
and Deputy State Transportation Engineer

TS: MS