New Jersey Department of Transportation
1035 Parkway Avenue, PO Box 600, Trenton, New Jersey 08625-0600

Baseline Document Change Announcement

ANNOUNCEMENT: **BDC25S-20**

DATE: **February 19, 2026**

SUBJECT: **Internal Traffic Control Plan (ITCP)**
- Revisions to Subpart 108.05.02 Part 3 of the 2019 Standard Specifications for Road and Bridge Construction

Subpart 108.05.02 Part 3 of the 2019 Standard Specifications for Road and Bridge Construction has been revised to require the submission of an ITCP as part of the safety program to separate, to the extent possible, work vehicles and equipment from workers on foot as per ANSI/ASSP A10.47.

The following revisions have been incorporated into the 2019 Standard Specifications via 2019 Standard Inputs, SI2019:

108.05.02 Safety Program
PART 3 IS CHANGED TO:

3. Elements of the Program. Include information and procedures for the following elements:

a. Chain of Command. Include the responsibilities of the management, supervisor, safety officer, and employees.

b. Traffic Control Coordinator. Include the name and contact information. Ensure that the traffic control coordinator meets the requirements specified in 159.03.01.

c. Environmental Manager. Include the name and contact information. Ensure that the environmental manager meets the requirements specified in 158.03.01.

d. Local Emergency Telephone Numbers. Include police, fire, medical, and, NJDEP hotline 1-877-WARN DEP (1-877-927-6337).

e. Procedures for Handling Emergencies. Provide guidelines for handling emergencies, including emergency action plans for accidents involving death or serious injury, property damage, fires, explosions, and severe weather. Include the emergency contact information of the Contractor's personnel responsible for handling emergencies.

f. Training Topics. Include regulatory and jobsite toolbox meetings. Include the documentation from the training and an attendance sheet for each.

g. Contractor's Safety Rules. Include housekeeping procedures and personal protective equipment requirements.

h. Employee Disciplinary Policy. Include the violation forms.

i. Safety Checklists. Include project safety-planning, emergency plans and procedures, documentation, and protective materials and equipment.

j. Forms. Include OSHA 300 Log and New Jersey Department of Labor L&I-1.

k. Security Policy Guidelines. Provide a copy for the office and for the Project Limits.

l. Hazard Communication Program. Provide the following:

1. The location of and instructions for understanding the MSDS. Ensure that the location and instruction are available to anyone within the Project Limits.
2. The person responsible for the hazard communication program and the method of informing personnel of the hazardous communication program. Include attendance sheets of hazard communication meetings.
3. When performing work that generates airborne crystalline silica, include engineering and work practice controls to limit exposure levels to at or below the permissible exposure limit according to 29 CFR 1910.1000 Table Z-3. Ensure that the program includes employee training and respiratory protection measures according to 29 CFR 1910.134 and control of the area when the permissible exposure limit is exceeded. Provide a trained and competent person, according to 29 CFR 1926.30, within the Project Limits at all times when performing work that produces airborne crystalline silica.

m. Additional Requirements. Provide additional procedures for Project specific topics including:

1. Compressed gas cylinders.
2. Confined spaces.
3. Cranes.
4. Electrical.
5. Equipment operators.
6. Fall protection.
7. Hand and power tools.
8. Hearing conservation.
9. Highway safety.
10. Lead.
11. Lock out/tag out.
12. Materials handling, storage, use, and disposal.
13. Night work.
14. Personal protective equipment.
15. Project entry and exit.
16. Respiratory protection.
17. Sanitation.
18. Signs, signals, and barricades.
19. Subcontractors.
20. Trenching.

n. Internal Traffic Control Plan (ITCP). Develop, submit, implement, and maintain an ITCP according to ANSI/ASSP A10.47 Section 6.5 and 6.6. At a minimum, ensure the plan includes:

1. A diagram showing internal vehicle and pedestrian routes, site layout, and hazard zones.
2. A listing of type and number of all on-site personnel and mobile equipment. Provide names of personnel upon request if needed after an accident.
3. A site-specific hazard identification checklist with corresponding mitigation measures aimed at reducing struck-by and related risks.
4. Safety notes emphasizing backing procedures, spotter usage, visibility aids, and run-over/back-over prevention.
5. A communication plan to ensure the ITCP is effectively communicated to all relevant workers, operators, subcontractors, and personnel. Distribute the communication plan at an onsite meeting or as otherwise directed by the RE.

Submit an updated ITCP plan during construction if any substantial changes, as determined by the RE, to site layout, access, or equipment occur. Ensure the updated plan is approved by the RE before implementation. Ensure plan modifications are communicated to affected personnel.

Provide a certification that the plan complies with ANSI/ASSP A10.47 Section 6.5, 6.6, and all associated requirements.

Within 15 days of receiving the safety program, the Department will determine if the safety program meets the requirements of the Contract. If the safety program does not meet the requirements, the Department will return the safety program for revision. Do not begin work within the Project Limits until the Department has approved the safety program.

The Contractor is responsible for implementing, monitoring, updating, and revising the safety program until Acceptance. Submit updates and revisions to the safety program to the RE for approval when new information, new practices or procedures, or changing site and environmental conditions necessitate modifications to protect site personnel.

Maintain a copy of the updated safety program, including the appropriate documentation associated with each element, within the Project Limits so that it is available to workers and other authorized persons entering the Project Limits. Provide copies of updates to the safety program to the RE.

If an incident occurs that requires a New Jersey Department of Labor & Workforce Development Form (L&I-1) to be submitted, send a copy to the Office of Capital Project Safety, New Jersey Department of Transportation, 1035 Parkway Avenue, P.O. Box 600, Trenton, NJ 08625-0600.

Failure to comply with the requirements set forth in the Elements of the Program will result in the RE suspending the Work wholly or in part as specified in 108.13 and suspending Estimates, as specified in 109.05, for failure of the Contractor to correct conditions unsafe for the workers or the general public, for failure to carry out provisions of the Contract, including but not limited to failure to develop, submit, implement, and maintain the ITCP.

Implementation Code R (ROUTINE)

Changes must be implemented in all applicable Department projects scheduled for Final Design Submission at least one month after the date of the BDC announcement. This will allow designers to make necessary plan, specifications, and estimate/proposal changes without requiring the need for addenda or postponement of advertisement or receipt of bids.

Recommended By:

Tina M. Shutz

Tina Shutz
Director
Capital Program Support

TS: MS

Approved By:

Parth Oza

Parth Oza, P.E.
Assistant Commissioner
Capital Program Management
and Deputy State Transportation Engineer